



ELECTION URGENT

GOVERNMENT OF WEST BENGAL  
OFFICE OF THE SUB DIVISIONAL OFFICER, RANAGHAT, NANDIA  
**Infrastructure Cell**  
RANAGHAT, Nadia.

**NOTICE INVITING PRE QUALIFICATION- CUM -TENDER (Two Cover System)**

**Tender Notice No.: 02 of 2020-2021 of SDO, Ranaghat**

Memo. No: 298 / ELEC

Date: 26/02/2021

e-tenders by two cover system are invited by the Officer-In-Charge, Infrastructure Cell in connection with the Assembly General Election'2021 on behalf of the Sub Divisional Officer, Ranaghat Nadia from eligible resourceful Contractors having experience in similar nature of work as per particulars given below. Tenders will be received through E-tender portal of Govt. of West Bengal Web Site.

1. Name of the work : Civil Works for providing infrastructure facilities at DC, RC, Commissioning, Vehicle and Counting etc. in connection with the Assembly General Election - 2021 at Ranaghat College at Ranaghat in the District of Nadia.
2. Estimate Value of work put to Tender : **Rs. 58,96,391.00**
3. Time of Completion of work : Strictly within the time schedule mentioned in the Schedule of works and as directed by the authority.
4. Contractors eligible to Submit tender :
  - a) Bonafied contractors having credentials in such type of work @ 40% of work value in a single work awarded not earlier than 2015-2016.
  - b) Bonafied contractors having credentials in such type of work @ 30% of work value in 2 (two) similar nature of work awarded not earlier than 2015-2016.
  - c) Bonafied contractors having credentials of one single running work of similar nature which has been completed to the extent of 80% or more and value of which is not less than the desired value at (a) above, awarded not earlier than 2015-2016.
6. Date and time for downloading of tender documents. : 26.02.2021 to 12.03.2021 up to 5.00 P.M. (as per Server clock)
7. Last date and time for submission of E-tender. : 12.03.2021 up to 5.00 P.M. (as per server clock)
8. Time & Date of Opening : **A) Technical bids :-**  
on 15.03.2021 after 10.00 A.M. (as per Server clock)  
**B) Financial bids :-** After evaluation of Technical bids.
9. Earnest Money : 2% of Estimated Amount (i.e Rs. 1,17,928.00) will be deposited in favour of Sub Divisional Officer, Ranaghat by the bidder through the following payment mode as per Finance Department **Order No. 3975-F(Y) dated 28th July, 2016 (Annexure - A)**
  - i) **Net Banking** (any of the banks listed in the ICICI Bank Payment gateway) in case of payment through ICICI bank payment gateway.
  - ii) **RTGS / NEFT** in case of offline payment through bank account in any bank.



10. Validity of the tender : The offer will remain valid for acceptance for 90 days from the date of receipt of tender or the election process is over
11. Guiding Schedule of rates for items of work : Approved rate of the District Authority
12. The Tender document and other relevant particulars (if any) may be seen by the intending tenders during office hours in the office of the Nadia Authority as well as from the web site <http://wbtenders.gov.in>
13. Throughout this document the terms and “tender” and their derivatives (bidder / tenderer / tendering etc.) are synonymous. . Page- 1 of 5
14. Conditional tender will be liable for rejection.
15. Time/ Cost over – run and consequent cost escalation for any material, labour etc. will not be allowed.
16. No mobilization advance/ secured advance will be allowed.
17. In case of inadvertent typographical mistake found in the specific price schedule of rates, the same will be treated to be so corrected as to confirm with the prevailing relevant schedule of rates and / or technically sanctioned estimate.
18. The intending tenderer is required to quote the rate in figure as well as in words mentioning percentage above/ below or AT PAR on the basis of the relevant price schedule of probable items with approximate quantities. The rate in the priced schedule is inclusive all taxes, loading, unloading, stacking, carriage of materials and all other incidental charges in this connection.
19. Contractor shall have to comply with the provisions of (a) the Contract labour (Regulation Abolition) Act, 1970 (b) Apprentice Act 1961 and (c) Minimum Wages Act, 1948 or the modification thereof or any other laws relating there to and the rules and order issued there under from time to time.
20. Bidders shall submit the copy of a) Valid PAN issued by the IT Deptt., Govt. of India and b) ) Valid 15 digit Goods and Services Taxpayer Identification Number (GSTIN) under **GST Act’ 2017** which will be valid up to the date of opening of the tender. Tax Invoice(s) needs to be issued by the supplier for raising claim under the contract showing separately the tax charged in accordance with the provisions of GST Act,2017. The intending tenderers will also have to produce credential documents of value as stated in annexure in a single work within last 5(Five) years and adequate financial capability audit report along with certificate of Chattered Accountant for last 3(three) years for both individual and companies and registration certificate issued by Registered of companies, West Bengal (in case of companies) along with the ‘Technical Bid’.
21. Representation in Tender in connection with tender submitted by Co- Operative Societies: -  
The Chairman and the Secretary or three directors including either the Chairman or the Secretary shall execute and sign all deeds, documents, tender papers as per act of the Bye- laws of the Co- operative Societies, failing which the tender will be liable for rejection. The copy of the last Audit report (Full) including copy of the minutes of last A.G.M. has to be submitted along with the ‘Technical Bid’. for verification of the authority.
22. No credential will be considered unless it is supported by payment certificate, work order and completion certificate mentioning the date of completion issued by the competent authority not below the rank of Executive Engineer or similar rank.
23. **Evaluation of Bid:** All tenderer or his authorized representative is requested to present personally during the opening of the tender and to sign the tender opening register as witness.  
The eligibility of a bidder will be ascertained on the basis of the uploaded documents in support of the minimum criteria as mentioned above. If any document submitted by a bidder is false, in such cases the eligibility of the bidder / tenderer will be out rightly rejected at any stage without any prejudice. While evaluation, the committee may summon of the tenders & seek clarification / information or additional supporting documents or original hard copies against copy/copies of any of the documents only which are already submitted/uploaded in the web portal by the bidders and if these are not produced by the intending Bidders within the stipulated time frame, his/her/their proposals will be liable for rejection.

**Objection/ Complaint regarding Non-Eligibility in Technical Bid Evaluation :** In case if there be any objection/complaint regarding Non-Eligibility in Technical Bid Evaluation, only intending Bidders or authorized persons on behalf of the Bidders may lodge objection/complaint along with specific authentic documents in support of their objection/complaint as a proof to the Notice Inviting Authority or Chairman, Tender Evaluation Committee within 48 (forty eight) hours from the publication time (uploading time in web portal) of the Technical Bid Evaluation and beyond that time schedule (i.e. after expiry of 48 hours) no objection/complaint will be entertained as well as without any specific authentic documents as a proof in support of lodged objection /



complaint, no objection or complaint in this regard will be entertained by the Tender Evaluation committee. On the other hand strict penal action may be taken against the respective Bidders for lodging false objection or complaint in obligatory attitude/ creating hindrance towards development works of the Govt. The detailed address of the complainant including e-mail/Fax number, mobile number & telephone number shall invariably have to be provided in their letter (through which if objection/complaint has to be lodged).

**Penalty for suppression / distortion of facts :** Submission of false /fabricated/ manufactured/incorrect documents or suppression of any running or incomplete works (including the work which is not declared as completed or any work in any other Department under the Govt. of India/Govt. of West Bengal/Govt. undertaking organizations, also work-order issued to the respective Bidder but work not started) or suppression or distortion of facts by the intending tenderers is strictly prohibited, yet, if it is found/proved prior to issue of letter of acceptance; his/her/their bid will summarily be rejected and the case may be referred to the appropriate authority for prosecution as per relevant IT & I.P.C. Act with forfeiture of earnest money forthwith to the Authority and penal action will be taken by the Deptt. as it deem fit and may be debarred from participation in any tender within the jurisdiction of Nadia district for a minimum period of 1 (one) year or more as it deem fit by the tender Inviting authority or competent Authority.

24. 1% Cess to be recovered from the Bill of the agency as per Govt. rule.  
25. The successful bidders will be selected based on overall lowest rate quoted by them.  
26. The authority reserves the right to reject or cancel any tender or all tenders without assigning any reason thereof. and no claim in this respect will be entertained.

The intending tenderers, at their own responsibility & risk is encouraged to visit and examine the site of works and its surroundings and obtain all information that may be necessary for preparing the bid and entering into a contract for the work as mentioned in the NIT. The cost of visiting the site shall be at the tender's own expenses.

27. Copy of this NIT along with other tender document may be obtained from the website <http://wbtenders.gov.in>

28. In the event of e-filling, intending bidder may download the tender documents from the website directly with the help of Digital Signature Certificate.

Preparation of Bids.

- (i) Documents comprising the Bid.

The Bid submitted by the bidder shall be in two separate parts.

**Part-I:** This shall be named 'Technical bid' and shall comprise of.

- i) 'Earnest Money' by online mode as per clause-9.

Authorized address and contact details of the bidder having the following information:-

Address of Communication:-

Telephone No.(land) \_\_\_\_\_ (Mo.) \_\_\_\_\_, Fax No.:- \_\_\_\_\_

E-Mail ID \_\_\_\_\_

- ii) Qualification information, supporting documents as specified in clause 4,19, 21,22,  
iii) Undertaking that the bid shall remain valid for the period specified in clause 10.  
iv) Any other information / documents required to be completed and submitted by bidders.  
v) An index stating the page Nos. of all documents submitted.

**Part-II:** It shall be named 'Financial Bid and shall comprise of.

- 1) Form of Bid.  
2) Priced bill of quantities for specified items of works.

Each part shall be separately sealed and marked in accordance with the instructions.

29. Audit Report of preceding 5 years  
30. The Contractor is liable to his own arrangement for necessary mechanical devices etc. as per requirement.  
31. **Refund of EMD :** As per Finance Deptt. **Order No. 3975-F(Y) dated 28th July, 2016 (Annexure - A).**

32. **Exemption of earnest Money:** Earnest Money for each and every category to be deposited compulsorily by all intending tenderers excepting the Labour Co-operatives who are exempted from Earnest Money against all tender. These societies, if selected through tender, will have to furnish requisite Security Deposit for performance of work. All registered Engineers' Co-operative Society participating in tenders should deposit Earnest money as usual failing which the tender will be treated as informal. Bidder eligible for exemption of EMD as per Govt. rules may avail the same and necessary documents regarding the exemption of EMD must be uploaded in the EMD folder of Statutory bid documents

33. **Submission of Bids :** The bidder shall place the two separate envelopes (Called inner envelopes) marked. "Technical Bid" and "Financial Bid" in one outer envelop. Mentioning the name of work N.I.T. No. and Sl. No. The inner envelopes will have marking as follows.



(i) 'Technical Bid' .

(ii) 'Financial Bid'

The contents of the 'Technical Bid' & 'Financial Bid' shall be as specified in clause 'Preparation of Bids' .

The inner and outer envelopes containing the Technical and Financial Bids shall.

- a) Be addressed to the Officer-In-Charge; Infrastructure Cell, Assembly General Election, Nadia.
- b) Bear the N.I.T No. , Sl. No. & Name of work.
- c) Be indicated the name & address of the Bidder in details i.e vill / Lane / P.O. / District etc. to enable the Bid to be returned unopened in case it is declared unopened as non-responsive.

34. **Late Bids:** Any Bid received after the stipulated time, will not be accepted.

35. **Bid Opening:** The received bids will be opened (Except those received late ) in the presence of the bidders/ bidder's representatives who choose to attend at the specified time, date & place . In the event of the specified date for the submission of bids being declared a holiday the bid will be opened at the appointed & location on the next working day.

\*. The technical bid shall be opened first.

\* In all other cases, the amount of Earnest Money, forms and validity shall be announced. Thereafter the bidders names and such other details as may be considered appropriate will be announced at the opening.

\*. Evaluation of technical bids with respect to qualification information other information in part-I of the bid shall be taken up and completed preferably within the prescribed period and list will be drawn up of the responsive bids whose financial bids are eligible for consideration.

\* A list of bidders, whose technical bids are found responsive, will be displayed in the office notice board prior to the schedule date of opening of financial bid. In case the specified date is deferred a corrigendum notice will be published and will be displayed in the office notice board.

\* At the time of the opening of the 'Financial Bids' the names of the eligible bidders will be announced. The financial bids of only those bidders will be opened. The remaining bids will be returned unopened to the bidders.

36. **Revocation / withdrawal of tender:** Revocation / withdrawal of tender by the participating bidder/s are not permissible. If the participating bidder/s or the lowest bidder on receipt of work-order do not take up the work or leave the work incomplete, a penal action will be taken by 'Black-listing in participation of tender' for one year or by forfeiture of his deposited earnest money, as decided by the authority.

37. **Compensation for delay in execution of work:** *As decided by the authority including forfeiture of earnest money.*

38. **Scope of work:**

- i. All works will be executed with due diligence, workmanship and up to the satisfaction of the authority. Any defective works will be dismantled forthwith. All materials brought to the site will be good quality to meet up the requirements of the specification of the work. Rejected materials will be removed from the venue within six hours of issue of such order.
- ii. Time is the essence of contract. All works will be completed positively within the specified time mentioned in the schedule. The authority reserves the right to take action including any penal action against him in case of unsuccessful completion of work in time. The work should be started immediately within 03 (three) days on the receipt of work order.
- iii. All materials brought to the site will be kept under the responsibility of the contractor. The authority will not be responsible for any kinds of damage, theft or any such incident.
- iv. The contractor will be responsible mend any damage to the existing structure beyond the schedule work without involving any cost therein. He is also responsible to make the venue premises clean, free from dumping any wastage materials and make the site in habitable condition upto the satisfaction of the authority.
- v. The authority reserves the right to alter any specification of work and the agency is liable to execute the work as per revised directions of the authority.
- vi. The quantity of work included in the schedule of work may vary as per requirement at site. Similarly any extra items which are not included in the schedule of works may be involved to meet up the requirement of the election process. The agency is liable to execute the work as per requirement upto the satisfaction of the authority.
- vii. The hire charges for furniture etc. will be allowed for the working periods only as mentioned in priced schedule of work. No idle dumping of such materials will be entertained.
- viii. All works will be executed abiding the rules and regulations in terms of COVID-19.




### 39. OTHER TERMS & CONDITIONS

Tender received later than specified date and time will not be considered. Tenders thus received will be opened as per schedule in presence of tenderer's who are intended to remain present. Such tenderers will please put their signature in the tender opening document as a token of witness during the opening process.

Tenderers are requested to fill in the tender documents correctly and completely, failing which the same will be liable for rejection according to the discretion of the Authority.

Tender submitted without earnest money will be treated as informal. No application for transfer of earnest money from one tender to another will be entertained.

The authority reserves the right not to accept the lowest offer and reject any tender without assigning any reason thereof. All particulars of work may be had in the Office of the undersigned up to 04:00 P.M. on all working days.


  
Sub Divisional Officer  
Ranaghat, Nadia

**Memo. No: 298/1(20)/ ELEC**

**Date: 26/02/2021**

#### Copy forwarded for wide circulation to :-

1. District Magistrate & District Election Officer, Nadia
2. The District Judge; Nadia
3. The Superintendent of Police, Nadia.
4. The Sub- Divisional Officer, Sadar / Tehatta / Kalyani Sub Division
5. The Officer-In Charge, District Election Cell, Nadia
6. The Nezarath Deputy Collector, Nadia.
7. The Executive Engineer, PWD, Nadia Div. Krishnagar
8. The Executive Engineer, Construction Div. PWD, Nadia, Krishnagar.
9. The Executive Engineer, Nadia Highway Div.- I , Krishnagar.
10. The Executive Engineer, WBSRDA, Nadia Division.
11. The Executive Engineer P.W. (C.B.) Directorate, Krishnagar Div.
12. The District Engineer, Nadia Zilla Parishad
13. The Post Master., Krishnagar HPO, Nadia
14. District Information & Cultural Officer, Nadia.
15. The DIO, NIC, Nadia-with a request to publish in the district web-site for wide circulation.
16. C.A. to the District Magistrate, Nadia.
17. C.A. to the Additional District Magistrate ( Gen /Dev / ZP / L& LR), Nadia.
18. Sri Binay Saha, Computer Assistant, NZP to upload in web site.
19. Block Development Officer, Santipur, Ranaghat-I, Ranaghat-II, Hanskhali & Krishnaganj Dev Block.
20. Office Notice Board.

  
Sub Divisional Officer  
Ranaghat, Nadia



## Price Schedule

**Civil Works for providing infrastructure facilities at DC, RC, Commissioning, Vehicle and Counting etc. in connection with the Assembly General Election - 2021 at Ranaghat College at Ranaghat in the District of Nadia.**

**Name of the venue : Ranaghat College, Nadia.**

Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
<b>A) EVM COMMISSIONING &amp; VVPAT</b>					
<b>87-Ranaghat Uttar Paschim, 89-Ranaghat Uttar Purba (SC), 90-Ranaghat Daksin (SC)</b>					
1.00	Hire and labour charges for supply of PVC chair (without arm) b) With out Cover : From 1 to 6 day	250 Nos	Rs. 21.22	Each	Rs. 5,305.00
2.00	Hire and labour charges for Supplying cushioned chairs for VIPs sitting arrangement i) From 1 to 6 day	12 Nos	Rs. 69.84	Each	Rs. 838.00
3.00	Hire and labour charges for supply of PVC Table (size 3'-00" X 2'-00"). a) With Table Cloth : From 1 to 6 day	1 Nos	Rs. 66.30	Each	Rs. 66.00
	b) Without Table Cloth : 1 to 6 day	120 Nos	Rs. 35.36	Each	Rs. 4,243.00
4.00	Hire and labour charges for supply of PVC Table (size 4'-00" X 3'-00"). b) Without Table Cloth : From 1 to 6 day	1 Nos	Rs. 44.20	Each	Rs. 44.00
5.00	Hire and labour charges for supply of good quality large size Sataranchi. i) From 1 to 6 day	6 Nos	Rs. 70.72	Each	Rs. 424.00
6.00	Supply of Labour (aged above 18 Years but not exceeding 50 years) at DC/RC/Counting venue etc. to serve different kinds of work as per requirement. (Duty hours be fixed to meetup the requirement in different span of the day ) [ Rate are provisional and restricted for Assembly General Election '2021 ]	12 MD	Rs. 300.00	MD	Rs. 3,600.00
7.00	II) Extra Charges per hour (beyond 8.0 hours per day)	12 Hrs	Rs. 30.00	Hrs	Rs. 360.00
<b>Comissioning SUB-TOTAL OF (A):</b>					<b>Rs. 14,880.00</b>

<b>B) DC &amp; RC(Civil)</b>					
<b>87-Ranaghat Uttar Paschim, 89-Ranaghat Uttar Purba (SC), 90-Ranaghat Daksin (SC)</b>					
1.00	Surface Dressing of the ground in any kind of soil including removing vegetation inequalities not exceeding 15 cm depth and disposal of the rubbish within a lead upto 75 m as directed.	300.000 M <sup>2</sup>	Rs. 10.00	M <sup>2</sup>	Rs. 3,000.00
2.00	Clearing compound premises of shurbs, plants, jungles etc. by cutting and removing as directed (Specific permission of Engineer-in-Charge prior to execution will be necessary). (Payment to be made on area cleared)	350.000 M <sup>2</sup>	Rs. 11.00	M <sup>2</sup>	Rs. 3,850.00
3.00	Uprooting and removing plants from the surface of walls parapet etc and making good damages. i) Medium size plant of girth of exposed stem above 75 mm. but not exceeding 150 mm. lift upto 6 mtr.	1.000 Nos	Rs. 60.00	Each	Rs. 60.00
4.00	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work). With carried earth arranged by the contractor within a radius exceeding 5 km. but not exceeding 10 km. including cost of carried earth.	1.000 M <sup>3</sup>	Rs. 491.79	M <sup>3</sup>	Rs. 492.00
5.00	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)	11.000 M <sup>3</sup>	Rs. 655.71	M <sup>3</sup>	Rs. 7,213.00
6.00	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	120.000 M <sup>2</sup>	Rs. 327.00	M <sup>2</sup>	Rs. 39,240.00



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
7.00	Dismantling R.C. floor, roof, beams etc. including cutting rods and removing rubbish as directed within a lead of 75 m. including stacking of steel bars. (a) In ground floor including roof.	0.50 M <sup>3</sup>	Rs. 1,956.00	M <sup>3</sup>	Rs. 978.00
8.00	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. a) In ground floor including roof.	0.50 M <sup>3</sup>	Rs. 447.00	M <sup>3</sup>	Rs. 224.00
8.01	b) In first floor	0.50 M <sup>3</sup>	Rs. 497.00	M <sup>3</sup>	Rs. 249.00
8.02	c) In second floor	0.50 M <sup>3</sup>	Rs. 547.00	M <sup>3</sup>	Rs. 274.00
9.00	Brick work with 1st class bricks in cement mortar (1:6) complete including dismantling and removing the same after election process is over. a) In ground floor	1.000 M <sup>3</sup>	Rs. 5,128.81	M <sup>3</sup>	Rs. 5,129.00
9.01	b) In first floor	1.000 M <sup>3</sup>	Rs. 5,239.82	M <sup>3</sup>	Rs. 5,240.00
9.02	c) In second floor	1.000 M <sup>3</sup>	Rs. 5,350.81	M <sup>3</sup>	Rs. 5,351.00
10.00	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) complete including dismantling and removing the same after election process is over. a) In ground floor.	10.000 M <sup>2</sup>	Rs. 671.56	M <sup>2</sup>	Rs. 6,716.00
10.01	b) In first floor.	1.000 M <sup>2</sup>	Rs. 683.57	M <sup>2</sup>	Rs. 684.00
10.02	c) In second floor.	55.000 M <sup>2</sup>	Rs. 695.56	M <sup>2</sup>	Rs. 38,256.00
11.00	75 mm. thick brick work with 1st class bricks set in cement, sand mortar (1:4) in ground floor including H.B. netting in every alternate layers. complete including dismantling and removing the same after election process is over. a) In ground floor.	1.000 M <sup>2</sup>	Rs. 460.43	M <sup>2</sup>	Rs. 460.00
11.01	b) In first floor.	1.000 M <sup>2</sup>	Rs. 472.43	M <sup>2</sup>	Rs. 472.00
11.02	c) In second floor.	75.000 M <sup>2</sup>	Rs. 484.43	M <sup>2</sup>	Rs. 36,332.00
12.00	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation and upto roof of ground floor/upto 4 m II. JSW/ JSPL/ SHYAM/ SRMB/ BMASL/ ELECTROSTEEL/SSL a) In ground floor.	0.050 MT	Rs. 55,458.19	MT	Rs. 2,773.00
12.01	b) In first floor.	0.050 MT	Rs. 55,888.20	MT	Rs. 2,794.00
12.02	c) In second floor.	0.050 MT	Rs. 56,318.19	MT	Rs. 2,816.00
13.00	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. a) Pakur Variety complete including dismantling and removing the same after election process is over. a) In ground floor.	0.500 M <sup>3</sup>	Rs. 5,211.97	M <sup>3</sup>	Rs. 2,606.00
13.01	b) In first floor.	0.500 M <sup>3</sup>	Rs. 5,306.97	M <sup>3</sup>	Rs. 2,653.00
13.02	c) In second floor.	0.500 M <sup>3</sup>	Rs. 5,401.97	M <sup>3</sup>	Rs. 2,701.00
14.00	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)  (a) 25 mm to 30 mm thick wooden shuttering as per decision & a) In ground floor.	1.000 M <sup>2</sup>	Rs. 330.00	M <sup>2</sup>	Rs. 330.00
14.01	b) In first floor.	1.000 M <sup>2</sup>	Rs. 348.00	M <sup>2</sup>	Rs. 348.00



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
14.02	c) In second floor.	1.000 M <sup>2</sup>	Rs. 366.00	M <sup>2</sup>	Rs. 366.00
14.03	B) 25 mm to 30 mm shuttering without staging in foundation	1.000 M <sup>2</sup>	Rs. 205.00	M <sup>2</sup>	Rs. 205.00
15.00	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]  (i) With 1:6 cement mortar, (c) 15 mm thick plaster a) In ground floor.	0.500 M <sup>2</sup>	Rs. 141.72	M <sup>2</sup>	Rs. 71.00
15.01	b) In first floor.	0.500 M <sup>2</sup>	Rs. 145.71	M <sup>2</sup>	Rs. 73.00
15.02	c) In second floor.	0.500 M <sup>2</sup>	Rs. 149.72	M <sup>2</sup>	Rs. 75.00
16.00	Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc. NOTE:Cement 0.152 cu.m per100 sq.m.	0.500 M <sup>2</sup>	Rs. 32.85	M <sup>2</sup>	Rs. 16.00
17.00	Applying decorative cement based paint of approved quality after preparing the surface including scraping the same thoroughly (plastered or concrete surface) as per manufacturer's specification. i)Two coats. a) In ground floor.	1.000 M <sup>2</sup>	Rs. 49.00	M <sup>2</sup>	Rs. 49.00
17.01	b) In first floor.	1.000 M <sup>2</sup>	Rs. 49.72	M <sup>2</sup>	Rs. 50.00
17.02	c) In second floor.	1.000 M <sup>2</sup>	Rs. 50.42	M <sup>2</sup>	Rs. 50.00
18.00	Hire & labour charges for erection of temporary structure as pandal with strong bamboo / Sal ballah post super structure with required height covered <b>with water proof tarpouline</b> , fixed tightly and secured by digging of holes and ties with rope etc. to stand steady during rain and wind, complete in all respect. All charges are including fitting, fixing transportation and dismantling after the end of the programme with other necessary materials required for the job complete including dismantling and removing the same after election process is over.  (a) with new cloth ceiling ,facia, side wall and post i) From 1 to 6 day	65000.000 Sft.	Rs. 17.68	Sft.	Rs. 1,149,200.00
18.01	(b) without new cloth ceiling ,facia, side wall and post i) From 1 to 6 day	19000.000 Sft.	Rs. 13.26	Sft.	Rs. 251,940.00
19.00	A) Erection of multiple counter having size (10'-00" X 13'-00") and 4'-6" heigh by bamboo partition with cloth within the above specified pandel (refer to Sl.No.-20) and <u>without wooden / plywood platform</u> (25mm thk.) from ground level complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	16000.000 Sft.	Rs. 6.19	Sft.	Rs. 99,040.00
19.01	B) Erection of multiple counter having size (10'-00" X 13'-00") and 4'-6" heigh bamboo partition with cloth within the above specified pandel (refer to Sl.No.-20) and, <u>with wooden / Plywood platform</u> (25mm thk.) raised 0'-6" from ground level complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1.000 Sft.	Rs. 13.88	Sft.	Rs. 14.00
19.02	C) Hire & labour charges for erection of <u>separate temporary structure</u> size (10'-00" X 13'-00") with strong bamboo / Sal ballah post super structure with required height covered with water proof tarpouline, fixed tightly and secured by digging of holes and ties with rope etc. to stand steady during rain and wind, with clothing at vertical wall and wooden / plywood platform 0'-6" raised from ground level complete in all respect. All charges are including fitting, fixing transportation and dismantling after the end of the programme with other necessary materials required for the job complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1.000 Sft.	Rs. 18.34	Sft.	Rs. 18.00



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
20.00	Construction of cubical stall by strong bamboo super structure with platform made with wooden runner, hard wood plank and back board with synthetic mat and cubical top covered by weather proofing terpoline etc. wall framed with wooden battens and plywood walls and fascia decorative by painting properly suitable arrangement by providing necessary chair, table and opening of each structure fitted with colapsible gate. Temporary structure of the said location to be removed and regain the original status of the ground as per decision and direction of E.I.C. for C.C. TV monitoring complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1.000 Sft.	Rs. 40.89	Sft.	Rs. 41.00
21.00	Hire & labour charges for erection of Platform <u>made by wooden plank 25mm thick / 12mm thk. plywood</u> and supported by wooden runner should be raised by minimum 0'-6" from the ground level. The platform should be strong enough to sustain adequate live load and dead load including all kind of transportation charges and making good the damaged ground/venue after dismantling the pandel.complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	15000.000 Sft.	Rs. 7.69	Sft.	Rs. 115,350.00
22.00	Hire & labour charges for erection of <b>Barricading work</b> to be done by the posting of <b>strong bamboo</b> with spacing 6'-00" centre to centre distance and vertical height above ground not less than 4'-00" with three lines of horizontal strong bamboo railing tightening by coir rope or other suitable materials for supporting adequate lateral load. including all kind of transportation charges and making good the damaged ground/venue after dismantling the pandel complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	10.000 R.Ft.	Rs. 8.40	R.Ft.	Rs. 84.00
23.00	Hire & labours charges for installation of collapsible gate as per specified location and including all kind of transportation charges complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	8.000 each	Rs. 419.91	each	Rs. 3,359.00
24.00	Hire and labour charges for covering of window and door of strong room with 4mm thk. Ply board with all supporting necessary battens complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	10.000 Sft.	Rs. 10.61	Sft.	Rs. 106.00
25.00	Hire and labour charges for installation of wooden platform raised 8'-00" height from the ground level used as watch tower by supporting all necessary horizontal & vertical bamboo structure complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1 Unit	Rs. 1,547.03	Unit	Rs. 1,547.00
26.00	Hire and labour charge of wall mount Display White Board with marker pen & duster (minimum size 3'-00" X 4'-00"). i) From 1 to 6 day	1 Unit	Rs. 1,246.46	Unit	Rs. 1,246.00
27.00	Hire and labour charges for good quality tarpulin for covering the Truck, keeping valuable materials on ground and other sitting arrangement purpose and covering the side wall of the pandal as a curtain complete including dismantling and removing the same after election process is over. a) From 1 to 6 day	75000.000 Sft.	Rs. 1.11	Sft.	Rs. 83,250.00



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
28.00	Hire and labour charges in fitting and fixing of wire mesh of 7'-00" high from the floor with necessary supporting and hanging arrangements by bamboo and wooden batten and covering the side upto 4'-00" from the floor by cloath tightened by coir string and nail complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1.000 Sft.	Rs. 34.48	Sft.	Rs. 34.00
29.00	Hire and labour charges for installation of 4mm ply partition upto 7'-00" height from the floor level supported by bamboo or wooden batten frame structure tightened enough with nail complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1.000 Sft.	Rs. 17.24	Sft.	Rs. 17.00
30.00	Hire and labour charges for installation of 4mm ply partition upto 11' height from the floor level supported by bamboo or wooden batten frame structure tightened enough with nail complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	350.000 Sft.	Rs. 19.45	Sft.	Rs. 6,808.00
31.00	Hire and labour charges for barricading by sand bag hight 5' hight and internal clear area 6'x6' with covering 8'-0" to 10'-0" ceiling height with one side slope structural shed with strong bamboo frame work including strong bamboo pillar & best tarpulin sheet only at the roof. All the structure should be tightened by the good quality coir string and others suitable materilas and the structuals should be supported by the lateral support from all four sides complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	5 Nos.	Rs. 3,933.88	Unit	Rs. 19,669.00
32.00	Hire and labour charges for installation of GCI sheet with wall supporting horizontal and vertical supporting bamboo structure with vertical height 10'-00" complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	7000.000 Sft.	Rs. 5.75	Sft.	Rs. 40,250.00
33.00	Hire and labour charges for supply of PVC chair (without arm) a) With Cover : From 1 to 6 day	1 Nos	Rs. 22.98	Each	Rs. 23.00
33.01	b) With out Cover : From 1 to 6 day	1200 Nos	Rs. 21.22	Each	Rs. 25,464.00
34.00	Hire and labour charges for Supplying cushioned chairs for VIPs sitting arrangement i) From 1 to 6 day	20 Nos	Rs. 69.84	Each	Rs. 1,397.00
35.00	Hire and labour charges for supply of PVC Table (size 3'-00" X 2'-00"). a) With Table Cloth : From 1 to 6 day	1 Nos	Rs. 66.30	Each	Rs. 66.00
35.01	b) Without Table Cloth : 1 to 6 day	1 Nos	Rs. 35.36	Each	Rs. 35.00
36.00	Hire and labour charges for supply of PVC Table (size 4'-00" X 3'-00"). a) With Table Cloth : From 1 to 6 day	3 Nos	Rs. 75.14	Each	Rs. 225.00
36.01	b) Without Table Cloth : From 1 to 6 day	200 Nos	Rs. 44.20	Each	Rs. 8,840.00
37.00	Hire and labour charges for supply of good quality standard size white table cloth. i) From 1 to 6 day	2 Nos	Rs. 35.27	Each	Rs. 71.00
38.00	Hire and labour charges for supply of steel made Tea Table with standerd size with covering by glass and cloath. i) From 1 to 6 day	2 Nos	Rs. 160.89	Each	Rs. 322.00
39.00	Hire and labour charges for supply of good quality sofa (6' length) for sitting purpose with cover and towel. i) From 1 to 6 day	3 Nos	Rs. 291.73	Each	Rs. 875.00
40.00	Hire and labour charges for supply of good quality large size Sataranchi. i) From 1 to 6 day	6 Nos	Rs. 70.72	Each	Rs. 424.00
41.00	Hire and labour charges for supply of good quality Coir mat (large size). i) From 1 to 6 day	250.000 Sft.	Rs. 3.76	Sft.	Rs. 940.00



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
42.00	Hire and labour charges for supply of good quality PVC waste drum (large size). i) From 1 to 6 day	10 Nos	Rs. 121.99	Each	Rs. 1,220.00
43.00	Hire and labour charges for Coffee vending machine (per day)	3 Nos	Rs. 353.61	Each	Rs. 1,061.00
44.00	Hire and labour charges for JCB including fuel lubricant and other necessary incentive.	3 Hrs	Rs. 1,069.66	Hrs	Rs. 3,209.00
45.00	Hire and labour charges for Tractor with Trolley including fuel, lubricant and other necessary incentive (carried upto 3 KM)	10 Trip	Rs. 1,105.02	Trip	Rs. 11,050.00
46.00	Hire charges of Road Roller including fuel, lubricant and other necessary incentive (working period 8 Hrs, per day.)	1 Day	Rs. 3,094.06	Day	Rs. 3,094.00
47.00	Hire and labour charge for Fire Extinguisher with all accessories. i) From 1 to 6 day	20 Unit	Rs. 1,856.44	Unit	Rs. 37,129.00
48.00	Hire and labor charge for installation / erection of wooden structure having size - (5'-00" X 3'-00") (section of wooden frame not less than 1"x1.5") for displaying Flex or other printed matter supplied by the department complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	25 Unit	Rs. 172.38	Unit	Rs. 4,310.00
49.00	Panel shutters of door and window, as per design (each panel consisting of single plank without joint), including fitting and fixing the same in position but excluding the cost of hinge and other fittings. In ground floor. (iii) 35mm thick shutters with 19mm thick panel of size 30 to 45 Cm. (b) Sisua, Gamar, Champ, Badam, Bhola, Mopgra, Hallack.	1.200 Sqft	Rs. 2,789.00	Sqft	Rs. 3,347.00
50.00	Hire and labour charges for providing "Drop Gate" with 15 cm dia salbullah of length not less than 8 meter including hoisting and fitting fixing with bolts and nuts to vertical posts (100 mm dia : 2 nos on each flank embedded 750 mm below G.L) and providing counter load of concrete or stone or iron block at the fulcrum end including painting two coats in alternate band providing 'STOP' plate, jute rope of necessary length etc complete including dismantling and removal as per direction of the Engineer in charge.	4 Nos	Rs. 626.00	###	Rs. 2,504.00
51.00	Supply of Labour (aged above 18 Years but not exceeding 50 years) at DC/RC/Counting venue etc. to serve different kinds of work as per requirement. (Duty hours be fixed to meetup the requirement in different span of the day) [Rate are provisional and restricted for Assembly General Election '2021]	12 MD	Rs. 300.00	MD	Rs. 3,600.00
51.01	II) Extra Charges per hour (beyond 8.0 hours per day)	12 Hrs	Rs. 30.00	Hrs	Rs. 360.00
52.00	Hire & labour charges for standard quality rack [External dimension: Length : 2.130 m, Height of ver. post upto 2.725 m, width : 0.610 m] with 6 nos vertical post of 2.725 m each made of ISA (35X35X5) mm and 4 (Four) horizontal layers made with 2 (Two) nos longitudinal member of length 2.10 m each made of ISA (35x35x5) mm, 3 (Three) nos transverse members of length 0.610 m each made of ISA (35x35x5) mm and 2 (Two) nos transverse members made of MS Flat of section-18x5 mm in every layer] tightening with necessary nuts and bolts etc. and making necessary holes as required. Shelves of each layer of the racks should be made of 8 mm thick approved quality ply board having sufficient strength to bear the load of BUs + CUs + VVPATs to be kept on them. Vertical post should be embedded by brick work (with 1:6 cement sand mortar) as and where required and making good the damaged floor after dismantling the same for keeping EVM, B.U., C.U. & VVPAT at strong room of all venue and removing the same after election process is over as per direction and upto the satisfaction of the authority. [Cost of brick work if required will be paid separately]  From Poll-7 day to Counting+2 Days	151 Unit	Rs. 12,965.43	Unit	Rs. 1,957,780.00



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
53.00	Hire & labour charges for erection of Hire & labour charges for <b>Barricading work</b> to be done by the <b>strong Sal bullah</b> vertical post diameter not less than 6" with spacing 6'-00" centre to centre distance and vertical height above ground not less than 4'-00" with three lines of horizontal strong bamboo railing tightening by coir rope or other suitable materials for supporting adequate lateral load including all kind of transportation charges and making good the damaged ground/venue after dismantling the pandel complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	10.000 R.Ft.	Rs. 10.52	R.Ft.	Rs. 105.00
54.00	Hire & labour charges for erection of view cutter, barricading height 7' supported by bamboo structure both vertical and horizontal with covering by cloath as per specified colour cloath including all kind of transportation charges and making good the damaged ground/venue after dismantling the pandel complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	5.000 Sft.	Rs. 2.52	Sft.	Rs. 13.00
DCRC (Civil)		SUB-TOTAL OF (B):		Rs. 4,011,633.00	

### C) DCRC(S&P)

#### 87-Ranaghat Uttar Paschim, 89-Ranaghat Uttar Purba (SC), 90-Ranaghat Daksin (SC)

1.00	Removing chokage in G.I. pipe including cleaning pipe. (i) 15 mm	20.00 Mtr	Rs. 7.00	Mtr	Rs. 140.00
1.01	(ii) 20 mm	10.00 Mtr	Rs. 7.00	Mtr	Rs. 70.00
1.02	(iii) 25 mm	10.00 Mtr	Rs. 7.00	Mtr	Rs. 70.00
2.00	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity. (a) Upto 1st story from G.L.	1 Nos	Rs. 96.00	Each	Rs. 96.00
3.00	Labour for punching hole in plastic water storage tank upto 50 mm dia.	2 Nos	Rs. 19.00	Each	Rs. 38.00
4.00	Supplying, fitting and fixing low-down cistern parts. (i) Internal fittings for cistern complete of approved make.	2 Nos	Rs. 284.00	Each Set	Rs. 568.00
5.00	Cleaning and disinfecting upto 2000 litre Water Tank including masonry reservoir.	5 Nos	Rs. 155.00	Each	Rs. 775.00
6.00	Supplying, fitting and fixing bib cock or stop cock. i) Polythene Bib Cock / Stop Cock with plastic inlet (EMCO / ATLAS or equivalent) 15 mm	36 Nos	Rs. 89.00	Each	Rs. 3,204.00
7.00	Supplying, fitting and fixing push cock of heavy quality and of approved make and brand. Polythene (i) 15 mm	5 Nos	Rs. 84.00	Each	Rs. 420.00
8.00	Supplying, fitting and fixing pillar cock of approved make. Polythene Piller Cock (EMCO / ATLAS or equivalent) : (i) 15 mm	5 Nos	Rs. 104.00	Each	Rs. 520.00
9.00	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste	5 Nos	Rs. 59.00	Each	Rs. 295.00
10.00	Supplying, fitting and fixing Waste fittings complete.	5 Nos	Rs. 44.00	Each	Rs. 220.00
11.00	Cleaning wash basin/ sink with acid.	12 Nos	Rs. 16.00	Each	Rs. 192.00
12.00	Dismantling and taking out lead / polythene waste pipe and refixing the	6 Nos	Rs. 29.00	Each	Rs. 174.00
13.00	Supplying, fitting and fixing Closet seat of approved make with lid and	3 Nos	Rs. 380.00	Each	Rs. 1,140.00
14.00	Cleaning silt of inspection pit.	4 Nos	Rs. 154.00	Each	Rs. 616.00
15.00	Cleaning silt of master trap pit.	2 Nos	Rs. 1,152.00	Each	Rs. 2,304.00
16.00	Refixing urinal.	1 Nos	Rs. 35.00	Each	Rs. 35.00
17.00	Cleaning E.P. or Anglo-Indian W.C. with acid.	1 Nos	Rs. 27.00	Each	Rs. 27.00
18.00	Cleaning I.P.W.C. with acid.	1 Nos	Rs. 19.00	Each	Rs. 19.00
19.00	Supplying, fitting & fixing PVC pipes of approved make of Schedule 80 (i) 15 mm i) From 1 to 6 day	30.00 Mtr	Rs. 40.40	Mtr	Rs. 1,212.00
19.01	(ii) 25 mm i) From 1 to 6 day	1.00 Mtr	Rs. 70.80	Mtr	Rs. 71.00
19.02	(iii) 40 mm				



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
	i) From 1 to 6 day	1.00 Mtr	Rs. 116.80	Mtr	Rs. 117.00
19.03	(iv) 80 mm i) From 1 to 6 day	1.00 Mtr	Rs. 179.23	Mtr	Rs. 179.00
20.00	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (i) 15 mm	5.00 Mtr	Rs. 101.00	Mtr	Rs. 505.00
20.01	(ii) 25 mm	1.00 Mtr	Rs. 177.00	Mtr	Rs. 177.00
20.02	(iii) 40 mm	1.00 Mtr	Rs. 292.00	Mtr	Rs. 292.00
21.00	Supplying fitting and fixing P.V.C. door shutter of approved quality & i) From 1 to 6 day	2.10 M <sup>2</sup>	Rs. 850.80	M <sup>2</sup>	Rs. 1,787.00
22.00	Making kutcha drain upto 450 mm. deep and upto 750 mm width to	50.00 Mtr	Rs. 29.17	Mtr	Rs. 1,459.00
23.00	Supply of polythene bucket (15 Lit) .on hire charges basis.	5 Nos	Rs. 97.24	Each	Rs. 486.00
24.00	Supply of polythene mug (1 Lit.) on hire charges basis	5 Nos	Rs. 22.10	Each	Rs. 111.00
25.00	Construction of temporary reservoir (3.00 X 1.00 X 0.75) Mtr. With masonry platform, digging of earthen soak-well (0.60 mtr dia and 1.00mtr deep) including cutting of kutcha drain (0.25 mtr X 0.25mtr X 6.00mtr - long) complete including dismantling and removing the same after election process is over.	1 Nos	Rs. 28,411.42	Each	Rs. 28,411.00
26.00	Sinking of 60.00 mtr. Deep temporary Tube-Well of size 100mm X 40mm using GI / UPVC / pipe etc. with 1 HP Pump on hire basis. complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1.00 Nos	Rs. 36,115.63	Each	Rs. 36,116.00
27.00	Sinking of 40.00 mtr. Deep and 40mm dia. temporary ordinary Tube-Well using GI / UPVC / pipe etc. with 1 HP Pump on hire basis. complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	6 Nos	Rs. 5,795.62	Each	Rs. 34,774.00
28.00	Construction of temporary Latrine. complete including dismantling and removing the same after election process is over.	33 Nos	Rs. 3,514.85	Each	Rs. 115,990.00
29.00	Construction of temporary drinking water supply system with PVC storage tank & masonry platform including kutcha drain (0.25 mtr X 0.25 mtr X 6.00 mtr - long) complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1.00 Nos	Rs. 14,819.66	Each	Rs. 14,820.00
30.00	Removal of rubbish,earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge	10.00 M <sup>3</sup>	Rs. 166.00	M <sup>3</sup>	Rs. 1,660.00
31.00	Fixing of bamboo post by digging holes in all shorts of soil and subsequent through repacking the same with spoils including the cost of one coat of coal tarring the embedded portion of the bamboo. complete including dismantling and removing the same after election process is over. a) Depth : 600mm.	10 Nos	Rs. 20.33	Each	Rs. 203.00
32.00	Strong bamboo posts, posts plates, rafters, ties etc. fitted and fixed complete with coir rope or nails as directed (Embedded portion of posts shall also be paid for against this item, cost of digging hole and repacking being paid for separately) complete including dismantling and removing the same after election process is over. a) 75mm dia bamboo.	10.00 Mtr	Rs. 40.66	Mtr	Rs. 407.00
32.01	b) 100mm dia bamboo.	10.00 Mtr	Rs. 53.93	Mtr	Rs. 539.00
33.00	Durma mat works strengthened with split bamboo placed both ways (225mm apart) both sides and tied together fitted and fixed complete (but excluding the cost of supporting frame work) complete including dismantling and removing the same after election process is over. i) Double durma mat works : In walls.	350.00 M <sup>2</sup>	Rs. 71.61	M <sup>2</sup>	Rs. 25,064.00
33.01	ii) Double durma mat works : In ceiling	1.00 M <sup>2</sup>	Rs. 92.82	M <sup>2</sup>	Rs. 93.00



SI No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
34.00	Double durma mat door and window strengthened with necessary split bamboo with strong outer frame and diagonals of bamboos and half bamboos complete including tying and handling the same. complete including dismantling and removing the same after election process is over.	1.00 M <sup>2</sup>	Rs. 116.69	M <sup>2</sup>	Rs. 117.00
35.00	Supplying and laying Polythene Sheet (150gm / sq.m.) on ceiling (over durma mat) on hire charges basis.	100.00 M <sup>2</sup>	Rs. 22.10	M <sup>2</sup>	Rs. 2,210.00
36.00	Carrying, supplying fitting, fixing in position of R.C.C. Squating with pan and syphonic system as per specification of approved size - 1.20M X 1.00M including digging sanitary pit of size - 0.90M dia X 1.20M height with proper dressing and levelling complete as per direction of E.I.C. complete including dismantling and removing the same after election process is over.	1 Nos	Rs. 1,060.82	Each	Rs. 1,061.00
37.00	Provision of sweeping and necessary cleaning of latrine and surrounding areas by spreading of bleaching powder time to time regularly as when required including supply of bleaching powder @ 250 gms. / Day. i) From 1 to 6 day	10 Day	Rs. 22.10	Day	Rs. 221.00
38.00	Dismantling temporary latrine with filling ditch by earth, burning bamboo & other materials, dismantling R.C.C. Squatting plate if necessary including dressing the site to its original condition and spreading of bleaching powder all complete and as per instruction of E.I.C.	25 Nos	Rs. 265.21	Each	Rs. 6,630.00
39.00	Labour for boring tube well of required dia. by water jet system through any type of soil strata including hire and labour charges for boring pipes, scaffolding, tools and plants as necessary and taking out them and lowering pipes, strainers, blind pipe etc. and fitting and fixing the same complete including bucket washing and other incidental works in the connection. The tube well should have a minimum 50 mm gap in between the outside of the tubewell pipe and the bore. (a) For depth upto 150 metre. (i) 40 mm dia. boring etc.	30.00 Mtr	Rs. 131.72	Mtr	Rs. 3,952.00
39.01	(ii) 50 mm dia. boring etc.	20.00 Mtr	Rs. 80.45	Mtr	Rs. 1,609.00
39.02	(iii) 100 mm dia. boring etc.	1.00 Mtr	Rs. 380.13	Mtr	Rs. 380.00
40.00	Taking out pipes of existing tube well including strainer etc. complete for portion of length: (i) 40 mm dia. : Upto 20 metre below G.L.	1.00 Mtr	Rs. 25.64	Mtr	Rs. 26.00
40.01	(ii) 40 mm dia. : Beyond 20 metre below G.L.	1.00 Mtr	Rs. 40.66	Mtr	Rs. 41.00
40.02	(iii) 100 mm dia. : Upto 20 metre below G.L.	1.00 Mtr	Rs. 71.61	Mtr	Rs. 72.00
41.00	Providing permits guarding and repair maintenance works of Tube-Wells round the clock including supply of necessary spare parts for each premises. i) From 1 to 6 day	3 Day	Rs. 884.02	Day	Rs. 2,652.00
42.00	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (a) 500 litre capacity as hire charge basis. i) From 1 to 6 day	5 Nos	Rs. 1,359.62	Each	Rs. 6,798.00
43.00	Supplying, fitting and fixing E.W.C. in white glazed vitreous chinaware of approved make complete in position with necessary bolts, nuts etc. (a) With 'P' trap	1 Nos	Rs. 1,421.00	Each	Rs. 1,421.00
44.00	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete, C.I. brackets including two coats of painting to bracket etc.	1 Nos	Rs. 1,015.00	Each	Rs. 1,015.00
45.00	Supplying, fitting and fixing 32 mm dia. Flush Pipe of approved make with necessary fixing materials and clamps complete. i) Polythene Flush Pipe	1 Nos	Rs. 155.00	Each	Rs. 155.00



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
46.00	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia. (iii) 600 mm long	1 Nos	Rs. 107.00	Each	Rs. 107.00
47.00	Hire charges for all materials for Tube-Well (including 6.00 mtr/9.00mtr stainers) sinking work including carriage.	1 Nos	Rs. 884.02	L.S.	Rs. 884.00
48.00	Hire charges of pump (1 HP) including lowering and necessary connections etc. all complete as per direction of E.I.C.	3 Day	Rs. 442.01	Day	Rs. 1,326.00
DCRC (S&P)		SUB-TOTAL OF ( C ):		Rs. 306,073.00	

#### D) COUNTING(Civil)

86-Shantipur, 87-Ranaghat Uttar Paschim, 88-Krishnaganj, 89-Ranaghat Uttar Purba (SC), 90-Ranaghat Daksin (SC)

1.00	Hire and labour charges for providing "Drop Gate" with 15 cm dia salbullah of length not less than 8 meter including hoisting and fitting fixing with bolts and nuts to vertical posts (100 mm dia : 2 nos on each flank embedded 750 mm below G.L) and providing counter load of concrete or stone or iron block at the fulcrum end including painting two coats in alternate band providing 'STOP' plate, jute rope of necessary length etc complete including dismantling and removal as per direction of the Engineer in charge complete including dismantling and removing the same after election process is over as per direction upto the satisfaction of the authority ..	12 Nos	Rs. 626.00	Each	Rs. 7,512.00
2.00	Hire & labour charges for erection of Barricading work to be done by the posting of <b>strong bamboo</b> with spacing 6'-00" centre to centre distance and vertical height above ground not less than 4'-00" with three lines of horizontal strong bamboo railing tightening by coir rope or other suitable materials for supporting adequate lateral load. including all kind of transportation charges and making good the damaged ground/venue after dismantling the pandel complete including dismantling and removing the same after election process is over as per direction upto the satisfaction of the authority. a) From 1 to 6 day	2000.00 R.Ft.	Rs. 8.40	R.Ft.	Rs. 16,800.00
21.00	Hire & labour charges for erection of <b>Barricading work</b> to be done by the <b>strong Sal bullah</b> vertical post of diameter not less than 6" with spacing 6'-00" centre to centre distance and vertical height above ground not less than 4'-00" with <b>three lines</b> of horizontal strong bamboo railing tightening by coir rope or other suitable materials for supporting adequate lateral load including all kind of transportation charges and making good the damaged ground/venue after dismantling the pandel complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	450.000 R.Ft.	Rs. 10.52	R.Ft.	Rs. 4,734.00
18.00	Hire & labour charges for erection of temporary structure as pandal with strong bamboo / Sal ballah post super structure with required height covered <b>with water proof tarpouline</b> , fixed tightly and secured by digging of holes and ties with rope etc. to stand steady during rain and wind, complete in all respect. All charges are including fitting, fixing transportation and dismantling after the end of the programme with other necessary materials required for the job complete including dismantling and removing the same after election process is over. (a) with new cloth ceiling ,facia, side wall and post i) From 1 to 6 day	2260.000 Sft.	Rs. 17.68	Sft.	Rs. 39,957.00
18.01	(b) without new cloth ceiling ,facia, side wall and post i) From 1 to 6 day	5000.000 Sft.	Rs. 13.26	Sft.	Rs. 66,300.00



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
5.00	Hire & labour charges for erection of view cutter, barricading height 7' supported by bamboo structure both vertical and horizontal with covering by cloath as per specified colour cloath including all kind of transportation charges and making good the damaged ground/venue after dismantling the pandel complete including dismantling and removing the same after election process is over. a) From 1 to 6 day	100.00 Sft.	Rs. 2.52	Sft.	Rs. 252.00
6.00	Hire & labours charges for installation of collapsible gate as per specified location and including all kind of transportation charges complete including dismantling and removing the same after election process is over. a) From 1 to 6 day	2 Each	Rs. 419.91	R,Ft.	Rs. 840.00
7.00	Hire and labour charges for covering of window and door of strong room with 4mm thk. Ply board with all supporting necessary battens complete including dismantling and removing the same after election process is over. a) From 1 to 6 day	10.00 Sft.	Rs. 10.61	Sft.	Rs. 106.00
25.00	Hire and labour charges for installation of wooden platform raised 8'-00" height from the ground level used as watch tower by supporting all necessary horizontal & vertical bamboo structutre complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1 Unit	Rs. 1,547.03	Unit	Rs. 1,547.00
27.00	Hire and labour charges for good quality tarpulin for covering the Truck, keeping valuable materials on ground and other sitting arrangement purpose and covering the side wall of the pandal as a curtain complete including dismantling and removing the same after election process is over. a) From 1 to 6 day	2500.000 Sft.	Rs. 1.11	Sft.	Rs. 2,775.00
10.00	Hire and labour charges in fitting and fixing of wire mesh of 7'-00" high from the floor with necessary supporting and hanging arrangements by bamboo and wooden batten and covering the side upto 4'-00" from the floor by cloath tightened by coir string and nail complete including dismantling and removing the same after election process is over. a) From 1 to 6 day	13500.000 Sqft	Rs. 34.48	Sqft	Rs. 465,480.00
29.00	Hire and labour charges for installation of 4mm ply partition upto 7'-00" height from the floor level supported by bamboo or wooden batten frame structure tightened enough with nail complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	200.000 Sft.	Rs. 17.24	Sft.	Rs. 3,448.00
30.00	Hire and labour charges for installation of 4mm ply partition upto 11' height from the floor level supported by bamboo or wooden batten frame structure tightened enough with nail complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	600.000 Sft.	Rs. 19.45	Sft.	Rs. 11,670.00
31.00	Hire and labour charges for barricading by sand bag hight 5' hight and internal clear area 6'x6' with covering 8'-0" to 10'-0" ceiling height with one side slope structural shed with strong bamboo frame work including strong bamboo pillar & best tarpulin sheet only at the roof. All the structure should be tightened by the good quality coir string and others suitable materilas and the structuals should be supported by the lateral support from all four sides complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	5 Nos.	Rs. 3,933.88	Unit	Rs. 19,669.00
32.00	Hire and labour charges for installation of GCI sheet with wall supporting horizontal and vertical supporting bamboo structure with vertical height 10'-00" complete including dismantling and removing the same after election process is over.				



Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
	i) From 1 to 6 day	2500.000 Sft.	Rs. 5.75	Sft.	Rs. 14,375.00
15.00	Hire and labour charges for supply of PVC chair (without arm)				
	a) Without Cover : From 1 to 6 day	1000.00 Nos	Rs. 21.22	Each	Rs. 21,220.00
	b) With Cover : From 1 to 6 day	12 Nos	Rs. 22.98	Each	Rs. 276.00
34.00	Hire and labour charges for Supplying cushioned chairs for VIPs sitting arrangement				
	i) From 1 to 6 day	12 Nos	Rs. 69.84	Each	Rs. 838.00
3.00	Hire and labour charges for supply of PVC Table (size 3'-00" X 2'-00").				
	a) With Table Cloth : From 1 to 6 day	5 Nos	Rs. 66.30	Each	Rs. 332.00
	b) Without Table Cloth : 1 to 6 day	5 Nos	Rs. 35.36	Each	Rs. 177.00
36.00	Hire and labour charges for supply of PVC Table (size 4'-00" X 3'-00").				
	a) With Table Cloth : From 1 to 6 day	2 Nos	Rs. 75.14	Each	Rs. 150.00
36.01	b) Without Table Cloth : From 1 to 6 day	300 Nos	Rs. 44.20	Each	Rs. 13,260.00
37.00	Hire and labour charges for supply of good quality standard size white table cloth.				
	i) From 1 to 6 day	5 Nos	Rs. 35.27	Each	Rs. 176.00
38.00	Hire and labour charges for supply of steel made Tea Table with standard size with covering by glass and cloth.				
	i) From 1 to 6 day	4 Nos	Rs. 160.89	Each	Rs. 644.00
39.00	Hire and labour charges for supply of good quality sofa (6' length) for sitting purpose with cover and towel.				
	i) From 1 to 6 day	4 Nos	Rs. 291.73	Each	Rs. 1,167.00
40.00	Hire and labour charges for supply of good quality large size Sataranchi.				
	i) From 1 to 6 day	6 Nos	Rs. 70.72	Each	Rs. 424.00
41.00	Hire and labour charges for supply of good quality Coir mat (large size).				
	i) From 1 to 6 day	250.000 Sft.	Rs. 3.76	Sft.	Rs. 940.00
42.00	Hire and labour charges for supply of good quality PVC waste drum (large size).				
	i) From 1 to 6 day	15 Nos	Rs. 121.99	Each	Rs. 1,830.00
43.00	Hire and labour charges for Coffee vending machine (per day)	1 Nos	Rs. 353.61	Each	Rs. 354.00
44.00	Hire and labour charges for JCB including fuel lubricant and other necessary incentive.	1 Hrs	Rs. 1,069.66	Hrs	Rs. 1,070.00
45.00	Hire and labour charges for Tractor with Trolley including fuel, lubricant and other necessary incentive (carried upto 3 KM)	1 Trip	Rs. 1,105.02	Trip	Rs. 1,105.00
46.00	Hire charges of Road Roller including fuel, lubricant and other necessary incentive (working period 8 Hrs, per day.)	1 Day	Rs. 3,094.06	Day	Rs. 3,094.00
48.00	Hire and labor charge for installation / erection of wooden structure having size - (5'-00" X 3'-00") (section of wooden frame not less than 1"x1.5") for displaying Flex or other printed matter supplied by the department complete including dismantling and removing the same after election process is over.				
	i) From 1 to 6 day	15 Unit	Rs. 172.38	Unit	Rs. 2,586.00
47.00	Hire and labour charge for Fire Extinguisher with all accessories.				
	i) From 1 to 6 day	10 Unit	Rs. 1,856.44	Unit	Rs. 18,564.00
48.00	Hire and labour charge of wall mount Display White Board with marker pen & duster (minimum size 3'-00" X 4'-00").				
	i) From 1 to 6 day	10 Unit	Rs. 1,246.46	Unit	Rs. 12,465.00
14.00	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. (vi) 100mm. X 50mm. X 1.25mm	30 Nos	Rs. 43.00	Each	Rs. 1,290.00
14.00	Iron socket bolt of approved quality fitted and fixed complete. (c) 150mm long x 10mm dia bolt.	10 Nos	Rs. 63.00	Each	Rs. 630.00
6.00	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	50.000 M <sup>2</sup>	Rs. 327.00	M <sup>2</sup>	Rs. 16,350.00




Sl No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
19.00	A) Erection of multiple counter having size (10'-00" X 13'-00") and 4'-6" height by bamboo partition with cloth within the above specified panel (refer to Sl.No.-20) and <u>without wooden / plywood platform</u> (25mm thk.) from ground level complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	3000.000 Sft.	Rs. 6.19	Sft.	Rs. 18,570.00
21.00	Hire & labour charges for erection of Platform <u>made by wooden plank 25mm thick / 12mm thk. plywood</u> and supported by wooden runner should be raised by minimum 0'-6" from the ground level. The platform should be strong enough to sustain adequate live load and dead load including all kind of transportation charges and making good the damaged ground/venue after dismantling the panel complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	2000.000 Sft.	Rs. 7.69	Sft.	Rs. 15,380.00
Counting (Civil)		SUB-TOTAL OF (D):		Rs. 788,357.00	

#### E) COUNTING (S&P)

86-Shantipur, 87-Ranaghat Uttar Paschim, 88-Krishnaganj, 89-Ranaghat Uttar Purba (SC), 90-Ranaghat Dakshin (SC)					
1.00	Removing chokage in G.I. pipe including cleaning pipe. (i) 15 mm	10.00 Mtr	Rs. 7.00	Mtr	Rs. 70.00
1.01	(ii) 20 mm	10.00 Mtr	Rs. 7.00	Mtr	Rs. 70.00
1.02	(iii) 25 mm	10.00 Mtr	Rs. 7.00	Mtr	Rs. 70.00
2.00	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity. (a) Upto 1st story from G.L.	1 Nos	Rs. 96.00	Each	Rs. 96.00
3.00	Labour for punching hole in plastic water storage tank upto 50 mm dia.	4 Nos	Rs. 19.00	Each	Rs. 76.00
4.00	Supplying, fitting and fixing low-down cistern parts. (i) Internal fittings for cistern complete of approved make.	1 Nos	Rs. 284.00	Each Set	Rs. 284.00
5.00	Cleaning and disinfecting upto 2000 litre Water Tank including masonry reservoir.	2 Nos	Rs. 155.00	Each	Rs. 310.00
6.00	Supplying, fitting and fixing bib cock or stop cock. i) Polythene Bib Cock / Stop Cock with plastic inlet (EMCO / ATLAS or equivalent) 15 mm	5 Nos	Rs. 89.00	Each	Rs. 445.00
7.00	Supplying, fitting and fixing push cock of heavy quality and of approved make and brand. Polythene (i) 15 mm	1 Nos	Rs. 84.00	Each	Rs. 84.00
8.00	Supplying, fitting and fixing pillar cock of approved make. Polythene Piller Cock (EMCO / ATLAS or equivalent) : (i) 15 mm	5 Nos	Rs. 104.00	Each	Rs. 520.00
9.00	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long	1 Nos	Rs. 59.00	Each	Rs. 59.00
10.00	Supplying, fitting and fixing Waste fittings complete. (b) Polythene : (i) 32 mm	1 Nos	Rs. 44.00	Each	Rs. 44.00
11.00	Cleaning wash basin/ sink with acid.	10 Nos	Rs. 16.00	Each	Rs. 160.00
12.00	Dismantling and taking out lead / polythene waste pipe and refixing the same after removing chokage including necessary bendings/ offsets and straightening and replacement of damaged parts, if any.	1 Nos	Rs. 29.00	Each	Rs. 29.00
13.00	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete. (a) E.W.C. - Plastic (hallow type) white	1 Nos	Rs. 380.00	Each	Rs. 380.00
14.00	Cleaning silt of inspection pit.	2 Nos	Rs. 154.00	Each	Rs. 308.00
15.00	Cleaning silt of master trap pit.	2 Nos	Rs. 1,152.00	Each	Rs. 2,304.00
16.00	Refixing urinal.	1 Nos	Rs. 35.00	Each	Rs. 35.00



Sl No.	Description of Work	Tentative Quantity		Approved Rate	Unit	Amount
17.00	Cleaning E.P. or Anglo-Indian W.C. with acid.	1	Nos	Rs. 27.00	Each	Rs. 27.00
18.00	Cleaning I.P.W.C. with acid.	5	Nos	Rs. 19.00	Each	Rs. 95.00
19.00	Supplying, fitting & fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM - 1785 as hire charges basis. (a) For Exposed Work (i) 15 mm i) From 1 to 6 day	5.00	Mtr	Rs. 40.40	Mtr	Rs. 202.00
19.01	(ii) 25 mm i) From 1 to 6 day	5.00	Mtr	Rs. 70.80	Mtr	Rs. 354.00
19.02	(iii) 40 mm i) From 1 to 6 day	5.00	Mtr	Rs. 116.80	Mtr	Rs. 584.00
19.03	(iv) 80 mm i) From 1 to 6 day	5.00	Mtr	Rs. 179.23	Mtr	Rs. 896.00
20.00	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made separately). (a) For Exposed Work (i) 15 mm	10.00	Mtr	Rs. 101.00	Mtr	Rs. 1,010.00
20.01	(ii) 25 mm	2.00	Mtr	Rs. 177.00	Mtr	Rs. 354.00
20.02	(iii) 40 mm	2.00	Mtr	Rs. 292.00	Mtr	Rs. 584.00
22.00	Making kutcha drain upto 450 mm. deep and upto 750 mm width to grade including trimming sides and beds, removing spoils to any distance and spreading, complete including dismantling and making good damages after election process is over.	15.00	Mtr	Rs. 29.17	Mtr	Rs. 438.00
23.00	Supply of polythene bucket (15 Lit) .on hire charges basis.	5	Nos	Rs. 97.24	Each	Rs. 486.00
24.00	Supply of polythene mug (1 Lit.) on hire charges basis	5	Nos	Rs. 22.10	Each	Rs. 111.00
29.00	Construction of temporary drinking water supply system with PVC storage tank & masonry platform including kutcha drain (0.25 mtr X 0.25 mtr X 6.00 mtr - long) complete including dismantling and removing the same after election process is over. i) From 1 to 6 day	1	Nos	Rs. 14,819.66	Each	Rs. 14,820.00
32.00	Strong bamboo posts, posts plates, rafters, ties etc. fitted and fixed complete with coir rope or nails as directed (Embedded portion of posts shall also be paid for against this item, cost of digging hole and repacking being paid for separately) complete including dismantling and removing the same after election process is over. a) 75mm dia bamboo.	10.00	Mtr	Rs. 40.66	Mtr	Rs. 407.00
32.01	b) 100mm dia bamboo.	10.00	Mtr	Rs. 53.93	Mtr	Rs. 539.00
35.00	Supplying and laying Polythene Sheet (150gm / sq.m.) on ceiling (over durma mat) on hire charges basis.	1.00	M <sup>2</sup>	Rs. 22.10	M <sup>2</sup>	Rs. 22.00
28.00	Construction of temporary Latrine. complete including dismantling and removing the same after election process is over.	15	Nos	Rs. 3,514.85	Each	Rs. 52,723.00
38.00	Dismantling temporary latrine with filling ditch by earth, burning bamboo & other materials, dismantling R.C.C. Squatting plate if necessary including dressing the site to its original condition and spreading of bleaching powder all complete and as per instruction of E.I.C.	15	Nos	Rs. 265.21	Each	Rs. 3,978.00

  
Assistant Engineer, PWD, Ranaghat Sub Division

  
Sub Divisional Officer, Ranaghat



SI No.	Description of Work	Tentative Quantity	Approved Rate	Unit	Amount
33.00	Durma mat works strengthened with split bamboo placed both ways (225mm apart) both sides and tied together fitted and fixed complete (but excluding the cost of supporting frame work) complete including dismantling and removing the same after election process is over. i) Double durma mat works : In walls.	120.00 M <sup>2</sup>	Rs. 71.61	M <sup>2</sup>	Rs. 8,593.00
		<b>Counting (S&amp;P)</b>	<b>SUB-TOTAL OF (E):</b>		<b>Rs. 91,567.00</b>

Comissioning	SUB-TOTAL OF (A):	=	Rs.14,880.00
DCRC (Civil)	SUB-TOTAL OF (B):	=	Rs.4,011,633.00
DCRC (S&P)	SUB-TOTAL OF ( C ):	=	Rs.306,073.00
Counting (Civil)	SUB-TOTAL OF (D):	=	Rs.788,357.00
Counting (S&P)	SUB-TOTAL OF (E):	=	Rs.91,567.00
		<b>TOTAL</b>	<b>= Rs.5,212,510.00</b>

<b>Add</b>	GST @ 12.00%	On	Rs.5,212,510.00	=	Rs.625,501.00
					<b>Rs.5,838,011.00</b>

<b>Add</b>	Cess @ 1.00%	On	Rs.5,838,011.00	=	Rs.58,380.00
					<b>Rs.5,896,391.00</b>